

Hamden Public Schools

West Woods Elementary School HVAC Unit Replacement, 11/2020

Scope:

The HVAC project scope shall include total replacement of (7) existing Trane gas fired packaged roof top units approximately 205 tons total.

Including, demolition, rigging, duct work cleaning.

Replace and upgrade existing Honeywell temperature controls including appropriate space sensing and building scheduling. Include remote access via school network to central HVAC department at HHS. Distech controls is only approved alternate to Honeywell.

Replace or modify existing VAVs and provide electric reheat as needed, include dehumidification cycle.

Provide all electrical installations as need.

Provide all roof curbing and flashings as needed.

Provide roof railings if need for maintenance access as required.

Provide all testing, balancing and commissioning of new systems.

Provide full training of systems to BOE maintenance staff, provide all closeout documents.